

**Preliminary Design Report** 

Prepared for: **City of Sylvania** 6730 Monroe Street Sylvania, OH 43560

April 11, 2023

Prepared by:

DGL Consulting Engineers, LLC 3455 Briarfield Boulevard, Suite E Maumee, Ohio 43537 www.dgl-ltd.com

**EDGE Group** 





# **Table of Contents**

EXECUTIVE SUMMARY
-------------------

# **Appendices**

Appendix A	Initial Stakeholder Material
Appendix B	Preliminary Design Plans
Appendix C	Streetscape Renderings
Appendix D	Estimated Construction Cost
Appendix E	2022 Collected Traffic Data

#### EXECUTIVE SUMMARY

DGL Consulting Engineers (DGL) was selected by the City of Sylvania to develop a plan for the rehabilitation of Main Street in downtown Sylvania. The plan builds on the vision established in the Downtown Sylvania Master Plan to create a streetscape design that addresses public realm, street, utility (water, sewer, electric) and sidewalk improvements. DGL's design team included EDGE, a planning and landscape architecture, urban design firm and JDRM, a mechanical, electrical and technology firm .

The project limits begin at the intersection of Main Street and Monroe Street and continue north approximately 1400' to the intersection of Main Street and Erie Street. The intersection of Main Street and Maplewood Avenue is included within the project scope, as it is located mid project. Maplewood Avenue from Main Street to Summit Street is also included within the study limits.

#### **Existing Conditions**

Main Street is a Minor Arterial within the project limits. The ADT for Main Street is 3792 per TIMS. The Peak Volumes and Truck Volumes were collected in the field and summarized on the 2022 Collected Traffic Data Figures in Appendix F. All three intersections along Main Street are currently signalized. Main Street is currently a two-way, one-lane roadway with some dedicated turn lanes at the intersections. The southern block between Monroe Street and Maplewood Avenue includes parallel parking on each side. The northern block between Maplewood Avenue and Erie Street does not include designated on-street parking.

The two blocks along Main Street also have different characteristics beyond street parking. The southern block has the more traditional downtown appearance with continuous storefronts and a 9' to 13' sidewalk width. The existing sidewalk includes patches of brick pavers and tree grates from prior streetscape improvements 40 years ago. Festive string lights also span across Main Street within this block. The northern block from Maplewood Avenue to Erie Street has a residential appearance that includes tree lawns, 4' wide sidewalks and further setbacks to commercial and residential fronts.

#### **Design Process**

DGL initiated the Study by performing a field survey and creating a base map of the existing infrastructure, topography and ownership. Traffic data was also collected at key locations to assist with any proposed recommendations.

An **initial stakeholders meeting** was held on August 24<sup>th</sup>, 2022 at City Council Chambers. The goal of this stakeholder meeting was to gauge the interests of the stakeholders and incorporate as many common interests into the Preliminary Design Plans. A PowerPoint presentation was delivered that included the anticipated schedule, work elements and design concept options for consideration. A comment form was also provided that included rankings for individual elements such as street parking, curbs, trees, pedestrian use and lighting.

The comment forms were collected, reviewed and summarized. Initial stakeholders meeting material, comment forms and summary of comments are included in Appendix A.

After the review of the comments, the DGL team prepared the Preliminary Design Plans that incorporated the majority of the stakeholders' comments. The preliminary plans are found in Appendix B – Preliminary Design Plans. The key elements included parallel parking on both sides, permanent parklets or seating and pedestrian amenities, wider sidewalk widths by reducing

roadway lane widths, increased parking spots and uniformity for both blocks along Main Street, uncurbed roadway, raised mid-block crossings, concrete sidewalk within pedestrian zones, and incorporation of trees.

DGL also reviewed options for the intersection at Main Street and Maplewood Avenue. Based on existing traffic data, the existing signal at Maplewood Avenue is not warranted. DGL reviewed a roundabout and a four way stop option for the intersection. The design team's preferred recommendation is the four way stop and elimination of dedicated turn lanes. This option adds pedestrian space and will help slow traffic, both of which were priorities to the stakeholders.

Options for the Main Street and Erie Street intersection were also reviewed by the design team. Based on existing traffic data, the existing signal at Erie Street is not warranted. A mini roundabout is the preferred recommendation for this location due to its minimal right of way impact, traffic calming features and ease of vehicular U-turns. Raised crosswalks, high-visibility pavement markings and overhead lighting are methods used for improved pedestrian safety at roundabouts. Rectangular rapid-flashing beacons can also be considered at both ends of each crosswalk and at the splitter islands to increase driver awareness of pedestrians.

EDGE prepared renderings and a 3D model video showing soft and hardscape options for the corridor. The renderings and video incorporate brick layouts for the parallel parking, additional seating and gathering areas at key locations, the use of branding for elements such as bike racks and tree box options. The streetscape renderings can be found in Appendix C.

A **second stakeholders meeting** was held at the City Council Chambers of February 1, 2023. This meeting was open house style with a brief recap of comments from the initial stakeholder meeting. The video prepared by EDGE was presented and key features explained during it's running. Time was provided during the meeting for individual Q&A between the design team and stakeholders. A one-page comment form was provided to the stakeholders. Appendix D includes a copy of the comment form and all comment forms received during and/or after the meeting.

The overall reaction to the Preliminary Design Plans is favorable. The additional parking, uncurbed roadway, additional sidewalk width and seating areas, mid-block crossings and tree locations appear to satisfy the stakeholder needs. There are concerns from a few stakeholders regarding the intersections at Maplewood Avenue and Erie Street.

#### **Estimated Construction Costs.**

The estimated construction cost is \$6,127,134. This cost includes a 10% contingency for items not quantified. There is also an 11% inflation based on a construction date in 2025. ODOT's Business Plan Inflation Calculator for CY 2023-2027 was used to determine the inflation rate. Appendix E includes the itemized Estimated Construction Cost for the Downtown Transportation Improvements Project. This cost references ODOT's Summary of Contracts Awarded for 2022 and recent City of Sylvania project bid tabs.

# Appendix A

**Initial Stakeholder Material** 



HORIZONTAL SCALE IN FEET

DESIGNER

DESIGNER

AMD

REVIEWER


SRC 08-10-22


PROJECT ID

22114


SHEET TOTAL


P.1 | 1






EXISTING TYPICAL SECTION
FROM MAPLEWOOD AVE TO ERIE ST











CONCEPTUAL TYPICAL SECTION

PARALLEL PARKING BOTH SIDES

CONCEPT A









CONCEPTUAL TYPICAL SECTION

ANGLED PARKING ONE SIDE

CONCEPT C









CONCEPTUAL TYPICAL SECTION

ANGLED PARKING BOTH SIDES

CONCEPT D









CONCEPTUAL TYPICAL SECTION

PARALLEL AND ANGLED PARKING

CONCEPT E









CONCEPTUAL TYPICAL SECTION

NO CURB WITH MEDIAN SLOTTED DRAIN

**CONCEPT F** 







CONCEPTUAL TYPICAL SECTION

NO PARKING

CONCEPT G

#### DGL Consulting Engineers, LLC

# Sylvania Downtown Improvements – Main Street

Date September 13, 2022

**Subject** Initial Stakeholder Meeting – Summary of Comments

**Project Number** 22114

Initial Stakeholder Meeting Public Attendees: 42

Comment Forms Received: 15

Concept Feedback Forms Received: 8

This document contains a summary of comments and survey results received from the public comment forms. Forms were distributed at the initial stakeholder meeting and posted online for the above referenced project.

#### **Category Ranking Results**

The following public opinions are summarized from the rankings provided under Question 2 on the Comment form:

- Preference of parking over no parking.
- Slight preference of angled parking over parallel parking.
- Slight preference of string lights over streetlamps.
- Slight preference of tables/seats over green space.
- Preference for corridor to be optimized for pedestrian use, with parking as second priority.
- High preference for the roadway to be uncurbed instead of having a standard 6" curb.
- Preference of the same number of trees. Very low preference for more trees.

#### **Concept Feedback**

These public opinions are summarized from the feedback provided on the Concept Feedback forms:

- Concept A (parallel both sides) had no strong positive and no negative feedback.
- Concept B (parallel one side) would be favorable if sidewalk widths are equal on both sides. Some concern for which side of the street parking would be located.
- Concept C (angled one side) is favorable to maximize parking. Some concern for which side of the street parking would be located. Some concern for angled parking.
- Concept D (angled parking both sides) is unfavorable since it reduces sidewalk widths.
- Concept E (angled and parallel parking) is unfavorable since people find it confusing.
- Concept F (uncurbed) is favorable since it has an uncurbed roadway.
- Concept G (no parking) is favorable if it were to provide a parking garage as well.

#### Comments

The following comments were provided on the Comment forms and Concept Feedback forms. The number of times it was mentioned by separate individuals is listed in parentheses.

- Main Street from Monroe to Erie should be uniform (4)
- Corridor should be pedestrian-focused with larger sidewalks (4)
- Parking garage (3)
- Easy-to-view storefronts (3)
- One-way traffic on Main Street (2)
- Slow down traffic (2)
- Raised mid-block crosswalk
- Outlets should be provided for events
- Prefer hanging baskets over large planters
- Recycle bins should be provided
- No stamped concrete on sidewalks
- More seating and gathering space for DORA users
- Need equal sidewalk space on each side of street
- Utilize Maplewood between Main & Summit for downtown events


#### Conclusions


The following items are recommended to be implemented with the Main Street Improvements Project:


- Roadway with parallel parking on both sides but utilizing curb bump outs and permanent
  parklets to provide seating and pedestrian amenities. These features will encourage traffic
  calming and create a pedestrian-focused corridor.
- Wider sidewalks provided by reducing lane widths.
- Parking spaces on both blocks (from Monroe to Erie) to create uniformity and provide more parking.
- Roadway with no curbs or minimal height curbs.
- Raised mid-block crosswalk at or near the existing crosswalk location. Consider an additional location between Maplewood and Erie.
- Concrete sidewalks. Decorative concrete/pavers may be used outside of the pedestrian thru
  zone.
- More views for existing architecture and storefronts. Consider tree reduction and/or changing tree types.
- String lights and streetlamps along entire corridor.
- Tables and seats to accommodate DORA customers and people at downtown events.


#### **END OF MEMO**













9/13/2022 4:05 PM Page 3 of 4







# Appendix B

**Preliminary Design Plans** 

CITY OF SYLVANIA - MAIN STREET IMPROVEMENTS CONCEPT A - PARALLEL PARKING

OLITING ENGINEERS

DESIGNER

AMD

REVIEWER

SRC 12-14-22

PROJECT ID

22114
SHEET TOTAL


STREET IMPROVEMENTS - PARALLEL PARKING CITY OF SYLVANIA - MAIN PARKING CONCEPT A

AMD SRC 12-14-22

22114

IIN SIKEEL IMIKKOVEIMIENIS

X\_RW\_Main - Plan 2 PAPERSIZE: 34x22 (in.) DATE: 12/14/2022 TIME: 2:37:12 PM USER: amd City of Svlvania - Downtown Improvements - Preliminary Study)\22114\400-Engineering\Roadwav\Sheets\Exhibits\22114 GP000 ConceptA.dgn





DESIGNER

AMD

REVIEWER

SRC 12-14-22

PROJECT ID

22114

SHEET TOTAL

P.3 5

HORIZONTAL SCALE IN FEET


# HORIZONTAL SCALE IN FEET MAIN ST MAIN ST [\*|\*] MAIN STREET IMPROVEMENTS MODEL: CLX\_F M:\22114 (Cit

CITY OF SYLVANIA - MAIN STREET IMPROVEMENTS PARKING CONCEPT A - PARALLEL PARKING

ESIGN AGENCY

DESIGNER AMD REVIEWER
SRC 12-14-22
PROJECT ID
22114

SHEET TOTAL P.4 5







DESIGNER AMD REVIEWER SRC 12-14-22 22114 SHEET TOTAL P.5 5

VANIA - MAIN STREET IMPROVEMENTS MAPLEWOOD AVE PARKING SYL CITY OF



Appendix C

**Streetscape Renderings** 













# Appendix D

**Estimated Construction Cost** 

# Estimate 22114

Estimated Cost:\$5,519,940.23

Contingency: 11.00%

Estimated Total: \$6,127,133.66

Preliminary Cost Estimate for Sylvania Downtown Transportation Improvements

Base Date: 02/28/23

Spec Year: 19

Unit System: E

Work Type: ASPHALT

Highway Type:

Urban/Rural Type: URBAN CLASS

Season:

County: LUCAS

Latitude of Midpoint: 0

Longitude of Midpoint: 0

District:

Federal/State Project Number:

Prepared by DGL CONSULTING ENGINEERS on 02/13/23

Page 2 of 6

9:36:10AM

Tuesday, February 28, 2023

Line # Item Number  Description Supplemental Description	Quantity	<u>Units</u>	<u>Unit Price</u>	<u>Extension</u>
Group 0001: ROADWAY  0001 201E11000  CLEARING AND GRUBBING	1.000	LS	\$5,000.00000	\$5,000.00
0002 201E20010 SPECIAL - TREE REMOVED, 4"-12"	28.000	EACH	\$280.00000	\$7,840.00
0003 201E21800 TREE REMOVED, 18"	6.000	EACH	\$406.91346	\$2,441.48
0004 202E23000 PAVEMENT REMOVED	6,922.960	SY	\$20.00000	\$138,459.20
0005 202E30000 WALK REMOVED	28,363.750	SF	\$1.48280	\$42,057.77
0006 202E32000 CURB REMOVED	2,807.280	FT	\$5.00000	\$14,036.40
0007 202E35100 PIPE REMOVED, 24" AND UNDER	824.000	FT	\$40.00000	\$32,960.00
0008 202E35100 PIPE REMOVED, 24" AND UNDER SANITARY	1,440.000	FT	\$40.00000	\$57,600.00
0009 202E35200 PIPE REMOVED, OVER 24"	1,000.000	FT	\$19.66399	\$19,663.99
0010 202E58000 MANHOLE REMOVED	2.000	EACH	\$683.28748	\$1,366.57
0011 202E58000 MANHOLE REMOVED SANITARY	5.000	EACH	\$700.00000	\$3,500.00
0012 202E58100 CATCH BASIN REMOVED	8.000	EACH	\$700.00000	\$5,600.00
0013 203E10000 EXCAVATION	1,200.000	CY	\$20.00000	\$24,000.00
0014 204E10000 SUBGRADE COMPACTION	7,762.780	SY	\$1.50000	\$11,644.17
0015 204E13000 EXCAVATION OF SUBGRADE	1,293.800	CY	\$20.00000	\$25,876.00
0016 608E10000 4" CONCRETE WALK	25,178.760	SF	\$8.50000	\$214,019.46

Line # Item Number  Description Supplemental Description	Quantity	<u>Units</u>	Unit Price	Extension
0017 608E15000 8" CONCRETE WALK AT ROUNDABOUT	5,779.450	SF	\$12.50000	\$72,243.13
0018 608E15000 8" CONCRETE WALK FOR DRIVES	4,679.990	SF	\$12.50000	\$58,499.88
0019 609E12000  COMBINATION CURB AND GUTTER, TYPE 2  CONCRETE GUTTER ONLY, ESTIMAT			\$21.95000 URB AND GUTTER	\$45,692.44
0020 609E26000 CURB, TYPE 6	1,708.000	FT	\$18.68839	\$31,919.77
0021 609E26000 CURB, TYPE 6 CONCRETE RIBBON, ESTIMATED 50%	1,567.670 6 COST OF T		\$9.40000 CURB	\$14,736.10
0022 609E57000 8" CONCRETE TRAFFIC ISLAND	670.000	SY	\$125.00000	\$83,750.00

# Total for Group 0001:\$912,906.36

# Group 0002: DRAINAGE

	0.00p 000=: 2::::::::::::::::::::::::::::::::				
	0023 605E11100 6" SHALLOW PIPE UNDERDRAINS	2,650.000	FT	\$12.00000	\$31,800.00
	0024 611E04400 12" CONDUIT, TYPE B	397.800	FT	\$125.00000	\$49,725.00
	0025 611E05900 15" CONDUIT, TYPE B	186.400	FT	\$150.00000	\$27,960.00
	0026 611E07400 18" CONDUIT, TYPE B	158.900	FT	\$175.00000	\$27,807.50
	0027 611E08900 21" CONDUIT, TYPE B	152.920	FT	\$210.00000	\$32,113.20
	0028 611E10400 24" CONDUIT, TYPE B	305.600	FT	\$250.00000	\$76,400.00
	0029 611E13400 30" CONDUIT, TYPE B	243.770	FT	\$300.00000	\$73,131.00
ľ	0030 611E16400 36" CONDUIT, TYPE B	218.580	FT	\$325.00000	\$71,038.50

				g,
Line # Item Number  Description Supplemental Description	Quantity	<u>Units</u>	Unit Price	Extension
0031 611E98150 CATCH BASIN, NO. 3	8.000	EACH	\$3,761.95420	\$30,095.63
0032 611E98180 CATCH BASIN, NO. 3A	8.000	EACH	\$3,326.65621	\$26,613.25
0033 611E99574 MANHOLE, NO. 3	9.000	EACH	\$4,121.43464	\$37,092.91
			Total for Group 0002:\$48	3,776.99
Group 0003: PAVEMENT				
0034 254E01000 PAVEMENT PLANING, ASPHALT CONCRETE	776.360	SY	\$8.01141	\$6,219.74
0035 301E56000 ASPHALT CONCRETE BASE, PG64-22, (449)	840.000	CY	\$171.96614	\$144,451.56
0036 304E20000 AGGREGATE BASE	1,177.000	CY	\$65.00000	\$76,505.00
0037 407E10000 TACK COAT	698.260	GAL	\$2.25143	\$1,572.08
0038 441E70000 ASPHALT CONCRETE SURFACE COURSE, T	242.000 YPE 1, (449), I		\$278.46418	\$67,388.33
0039 441E70300 ASPHALT CONCRETE INTERMEDIATE COUR	245.000 SE, TYPE 2, (		\$213.96110	\$52,420.47

Total for Group 0003:\$1,148,686.78

# Group 0004: UTILITIES

690E98200

0040

SPECIAL - BRICK PAVERS

0041 611E04400	1,440.000	FT	\$74.38312	\$107,111.69
12" CONDUIT, TYPE B SANITARY	Note, trunk lines were lining, thus reducing the		2016. Laterals may be a candidate for dary Cost.	cleanout and
0042 611E99574 MANHOLE, NO. 3 SANITARY	5.000	EACH	\$4,121.43464	\$20,607.17
0043 638E01204 8" WATER MAIN DUCTILE	1,545.250 I IRON PIPE ANSI CLASS 53, PUS		\$120.00000 INT S AND FITTINGS	\$185,430.00

\$40.00000

20,003.240 SF

\$800,129.60

33.000

EACH

\$364.09675

625E75500

LIGHT POLE FOUNDATION REMOVED

0056

\$12,015.19

DGL Consulting Engineers, LLC

Line # Item Number Quantity Units Unit Price

<u>Description</u> Quantity <u>Units</u>

**Extension** 

Total for Group 0006:\$351,881.69

Group 0007: INCIDENTALS

**Supplemental Description** 

Estimate: 22114

 0057
 614E11000
 1.000
 LS
 \$100,000.00000
 \$100,000.00

 MAINTAINING TRAFFIC

 0058
 623E10000
 1.000
 LS
 \$30,000.00000
 \$30,000.00

 CONSTRUCTION LAYOUT STAKES AND SURVEYING

0059 624E10000 1.000 LS \$200,000.00000 \$200,000.00

Total for Group 0007:\$330,000.00

Group 0009: LANDSCAPE

0061 661E99000 1,256,956.000 LS \$1.00000 \$1,256,956.00

SPECIAL - LANDSCAPING

Total for Group 0009:\$1,256,956.00

Group 0010: CONTINGENCY

 0060
 1.000
 \$501,812.74800
 \$501,812.75

 10% Contingency

Total for Group 0010:\$501,812.75


# Sylvania Downtown Streetscape


Date				2/16/2023
Item	Quantity	Unit	Unit Cost	Total Cost
<u>IMPROVEMENTS</u>				
Planter curb	3265	5 LF	\$25.00	\$81,625.00
Brick pavers Included in Roadway estim	nate 18,352.20	) SF	\$30.00	\$0.00
Planter Pots	19	9 EA	\$500.00	\$9,500.00
Benches	13	B EA	\$2,500.00	\$32,500.00
Tables and seating (public)	12	2 EA	\$6,000.00	\$72,000.00
Litter Receptacles	12	2 EA	\$1,500.00	\$18,000.00
Fence	65	5 LF	\$85.00	\$5,525.00
Bike Rack (1 set is 3)	8	8 set	\$1,000.00	\$8,000.00
Bollards	10	) EA	\$250.00	\$2,500.00
Masonry seat wall (18" hgt)	228	3 LF	\$1,000.00	\$228,000.00
Underdrains	2463	3 LF	\$12.00	\$29,556.00
<u>Lighting</u> s	ee Electrical Enginee	r		\$0.00
Subtotal				\$487,206.00
<u>LANDSCAPE</u>				
Shade trees		7 EA	\$700.00	\$53,900.00
Plants	6,180	) SF	\$20.00	\$123,600.00
Planting soil media	6,180	O CY	\$90.00	\$556,200.00
Mulch	515	5 CY	\$70.00	\$36,050.00
Subtotal				\$769,750.00
ESTIMATED SUBTOTAL				\$1,256,956.00
25% Contingency reduced to 10%				\$314,239.00
TOTAL CONSTRUCTION COST				\$1,571,195.00
11% INFLATED CONSTRUCTION COST				\$1,744,026.45

This estimated was calculated by EDGE and inserted into the overall estimate. See Group 9 - Landscape.

# Appendix E

**2022 Collected Traffic Data** 





# STUDY AND ANALYSIS INFORMATION

Municipality: Sylvania County: Lucas **ODOT Engineering** 2 District:

**Traffic Volumes Obtained By: DGL Consulting Engineers** 12/21/2022 **Analysis Date:** Agency/ Company Name Performing **DGL Consulting Engineers Warrant Analysis:** 

#### **Analysis Information**

7/20/2022 **Data Collection Date:** Day of the Week: Wednesday

Is the intersection in a built-up area of an isolated community of <10,000 population?

No

**Existing Traffic Signal at intersection:** 

Yes

**Total Number of Approaches at Intersection:** 

#### **Major Street Information**

Major Street Name and Route Number: Main Street

**Major Street Approach Direction:** 

N-Bound S-Bound

Number of Thru Lanes on Each Major Street Approach:

LANE(S)

Speed Limit or 85th Percentile Speed on the Major Street\*:

**MPH** 

\*Unknown assumes below 45 mph

#### **Minor Street Information**

Minor Street Name and Route Number: Erie Street Minor Street Approach Configuration

E-Bound W-Bound



Number of Thru Lanes on Each Minor Street Approach: Apply Right Turn Lane Reduction\*:

LANE(S) No

\*Right Turn Lane Reduction Shall be used for Warrants 1, 2, & 3 for New ODOT Signals. Please refer to TEM 402-3.2 for clarification and criteria under which Right Turn Reduction is not required.

# TRAFFIC SIGNAL WARRANT ANALYSIS FINDINGS

Warrant					
	Applicable?	Satisfied?	Notes and Comments:		
Warrant 1, Eight-Hour Vehicular Volume	Yes	No			
Warrant 2, Four-Hour Vehicular Volume	Yes	No			
Warrant 3, Peak Hour	Yes	No	Signals installed under Warrant 3 should be traffic actuated.  Peak Hour  4:15 PM  5:15 PM		
For Warrants 1-3, new	ODOT signal	s must be bas	sed off of 100% volume thresholds (TEM 402-3.2)		
Warrant 4, Pedestrian Volume	Yes	No	If this warrant is met, and a traffic control signal is justified by an engineering study, the traffic control signal shall be equipped with pedestrian signal heads complying with the provisions set forth in Chapter 4E of the OMUTCD.  Peak Hour 4:00 PM 5:00 PM		
Warrant 5, School Crossing	No		N/A		
Warrant 6, Coordinated Signal System	No		(Shall not be used as the sole warrant in the analysis)		
Warrant 7, Crash Experience	No		If this is the sole warrant, signal must be semi-actuated with control devices which provide proper coordination if installed at an intersection within a coordinated system and normally should be fully traffic actuated if installed at an isolated intersection.		
Warrant 8, Roadway Network	No		(Shall not be used as the sole warrant in the analysis)		
Warrant 9, Intersection Near a Grade Crossing	No		Figure 4C-9		
Multi-Way Stop Warrant	Yes	No	May be used as an interim measure if traffic signal warrants are satisfied.		

The satisfaction of a traffic signal warrant or warrants shall not in itself require the installation of a traffic control signal.

If no warrants are satisfied, additional options may be considered:

- 1. An engineering study, performed by a firm prequalified by ODOT for signal design, if approved by the ODOT district, may be used to justify a new signal installation or retention of an existing signal that otherwise does not meet the published warrants. An example of such an instance is a traffic signal in proximity to a railroad crossing that serves to reduce queuing across the tracks.
- 2. According to TEM 402-2, If the actual turning movement counts fail to satisfy a signal warrant, it may be acceptable to use traffic volumes projected to the second year after project completion. The **Modeling and Forecasting Section** should provide the projected traffic volumes.
- 3. A pedestrian hybrid beacon may be considered for installation to facilitate pedestrian crossings at a location that does not meet traffic signal warrants (see Chapter 4C of TEM) or at a location that meets traffic signal warrants under Sections 4C.05 and/or 4C.06 but a decision is made to not install a traffic control signal. **Please fill inputs on PHB Score Sheet and submit to ODOT.**

Considerations such as geometrics and lack of sight distance generally have not been accepted in lieu of satisfying signal warrants. These considerations may allow an otherwise unwarranted traffic signal to be retained at **100** percent local cost. Please review TEM 402-4 for details.

-	Conclusion: Do Not Retain Existing Traffic Signal	
Notes:		

# STUDY AND ANALYSIS INFORMATION

Municipality: Sylvania County: lucas **ODOT Engineering** 2 District:

**Traffic Volumes Obtained By: DGL Consulting Engineers** 12/21/2022 **Analysis Date: Agency/ Company Name Performing Warrant Analysis:** 

#### **Analysis Information**

7/20/2022 **Data Collection Date:** Day of the Week: Wednesday

Is the intersection in a built-up area of an isolated community of <10,000 population?

No

**Existing Traffic Signal at intersection:** 

Yes

**Total Number of Approaches at Intersection:** 

#### **Major Street Information**

Major Street Name and Route Number: Main Street

N-Bound **Major Street Approach Direction:** S-Bound

Number of Thru Lanes on Each Major Street Approach: LANE(S)


Speed Limit or 85th Percentile Speed on the Major Street\*: 35 **MPH** 

\*Unknown assumes below 45 mph

#### **Minor Street Information**

Minor Street Name and Route Number: Maplewood Ave Minor Street Approach Configuration

E-Bound W-Bound





Number of Thru Lanes on Each Minor Street Approach: Apply Right Turn Lane Reduction\*:

LANE(S) No

\*Right Turn Lane Reduction Shall be used for Warrants 1, 2, & 3 for New ODOT Signals. Please refer to TEM 402-3.2 for clarification and criteria under which Right Turn Reduction is not required.

# TRAFFIC SIGNAL WARRANT ANALYSIS FINDINGS

Warrant						
	Applicable?	Satisfied?	Notes and Comments:			
Warrant 1, Eight-Hour Vehicular Volume	Yes	No				
Warrant 2, Four-Hour Vehicular Volume	Yes	No				
Warrant 3, Peak Hour	Yes	No	Signals installed under Warrant 3 should be traffic actuated.  Peak Hour  4:45 PM  5:45 PM			
For Warrants 1-3, new	ODOT signal	s must be bas	sed off of 100% volume thresholds (TEM 402-3.2)			
Warrant 4, Pedestrian Volume	No		If this warrant is met, and a traffic control signal is justified by an engineering study, the traffic control signal shall be equipped with pedestrian signal heads complying with the provisions set forth in Chapter 4E of the OMUTCD.  Peak Hour  4:45 PM  5:45 PM			
Warrant 5, School Crossing	No		N/A			
Warrant 6, Coordinated Signal System	No		(Shall not be used as the sole warrant in the analysis)			
Warrant 7, Crash Experience	No		If this is the sole warrant, signal must be semi-actuated with control devices which provide proper coordination if installed at an intersection within a coordinated system and normally should be fully traffic actuated if installed at an isolated intersection.			
Warrant 8, Roadway Network	No		(Shall not be used as the sole warrant in the analysis)			
Warrant 9, Intersection Near a Grade Crossing	No		Figure 4C-9			
Multi-Way Stop Warrant	Yes	No	May be used as an interim measure if traffic signal warrants are satisfied.			

The satisfaction of a traffic signal warrant or warrants shall not in itself require the installation of a traffic control signal.

If no warrants are satisfied, additional options may be considered:

- 1. An engineering study, performed by a firm prequalified by ODOT for signal design, if approved by the ODOT district, may be used to justify a new signal installation or retention of an existing signal that otherwise does not meet the published warrants. An example of such an instance is a traffic signal in proximity to a railroad crossing that serves to reduce queuing across the tracks.
- 2. According to TEM 402-2, If the actual turning movement counts fail to satisfy a signal warrant, it may be acceptable to use traffic volumes projected to the second year after project completion. The **Modeling and Forecasting Section** should provide the projected traffic volumes.
- 3. A pedestrian hybrid beacon may be considered for installation to facilitate pedestrian crossings at a location that does not meet traffic signal warrants (see Chapter 4C of TEM) or at a location that meets traffic signal warrants under Sections 4C.05 and/or 4C.06 but a decision is made to not install a traffic control signal. **Please fill inputs on PHB Score Sheet and submit to ODOT.**

Considerations such as geometrics and lack of sight distance generally have not been accepted in lieu of satisfying signal warrants. These considerations may allow an otherwise unwarranted traffic signal to be retained at **100** percent local cost. Please review TEM 402-4 for details.

-	Conclusion: Do Not Retain Existing Traffic Signal	
Notes:		